

RENCANA ANGGARAN BIAYA PEKERJAAN
PERBAIKAN SENSOR WATER LEVEL RESERVOIR I
LOKASI: BOOSTER PUMP SEI AGUL

NO	URAIAN PEKERJAAN	VOL	SAT	ANL	HRG. SAT. (Rp)	JLH. HARGA (Rp)	SUB TOTAL (Rp)
I	MATERIAL						
1	Endress Hauser Hydrostatic Level measurement Waterpilot FMX21 - AA121HGD10A Out : 4 -20 mA Cable : 10 m range : 0 - 1 bar	1,0	unit	Hitung	20.794.801,06	20.794.801,06	
2	Asesoris pemasangan (skun, kabel ties, paku klem kabel, isolasi scotch)	1,0	Ls	Hitung	200.000,00	200.000,00	
							20.994.801,06
II	Biaya Pelaksanaan						
1	Pemasangan sensor di lokasi, kalibrasi, dan setting plc	1,0	unit	Hitung	1.000.000,00	1.000.000,00	
							1.000.000,00
Jumlah biaya pelaksanaan							21.994.801,06
Terbilang : Dua Puluh Satu Juta Sembilan Ratus Sembilan Puluh Lima Ribu Rupiah						Grand Total Dibulatkan	21.994.801,06 21.995.000,00

Disahkan oleh :

Ali Ismail Siregar
Kadiv. Perencanaan Air Minum

Diketahui oleh :

Dedi Gusman
Kadiv. Transmisi Distribusi

Medan, April 2024

Dihitung oleh


Julfan Fadhi
Kabid. Operasional Pompa