

BREAKDOWN PEMBUATAN 1 (SATU) UNIT TIANG GAWANG BESI WF UKURAN 1'00 x 1'00 TINGGI 2'00

A	Material	Vol	sat	analisa	harga satuan	jumlah
1	Besi WF Ukuran 200x100x5,5x8 mm (P=12 m) (0,100x0,008x12x2x7850) + (0,184x0,0055x12x7850)	246,05	Kg	hitung	26.400,00	6.495.730,56
					Jumlah A	6.495.730,56
B	Pelaksanaan					
1	Pemotongan Besi WF= 8 mm 11 x potong ((0,184+0,1+0,1)*11)	4,22	M'	tabel	71.850,00	303.494,40
2	Pengelasan Besi WF = 8 mm 14 x las ((0,184+0,1+0,1)*14)	5,38	M'	tabel	505.300,00	2.716.492,80
3	Gerenda & penyetelan	1,00	Bh	Ls	50.000,00	50.000,00
					sub total B:	3.069.987,20
					Jumlah A + B	9.565.717,76

