

**RENCANA ANGGARAN BIAYA PEKERJAAN
PERBAIKAN PANEL ALARM PLN DI BOOSTER PUMP PADANG BULAN**

NO	URAIAN PEKERJAAN	VOL	SATUAN	ANALISA	HARGA SATUAN (Rp)	JUMLAH HARGA (Rp)
I <u>Material</u>						
1	Box panel 30 x 40 x 20 cm indoor	1,0	unit	Hitung	500.000,00	500.000,00
2	Pilot lamp with voltmeter 220VAC	3,0	unit	Hitung	75.000,00	225.000,00
3	MCB 4 pole - 32 A CHINT (setara)	1,0	unit	Hitung	250.000,00	250.000,00
4	NYHHY 4 x 1,5mm SUPREME (1 roll = 50m)	1,0	roll	Hitung	1.800.000,00	1.800.000,00
5	Phase Failure Relay CHINT XJ3-D	1,0	pcs	Hitung	600.000,00	600.000,00
6	Selector switch 4 pole 25mm SALZER	1,0	pcs	Hitung	250.000,00	250.000,00
7	Sirene Alarm EWIG ms-290	1,0	pcs	Hitung	300.000,00	300.000,00
8	Relay MK3P OMRON Original lengkap socket	1,0	bh	Hitung	200.000,00	200.000,00
9	Asesoris Pemasangan (terminal kabel, dudukan soket, Isolasi, kabel ties, klem kabel, fischer)	1,0	Ls	Ls	300.000,00	300.000,00
					Jumlah I	4.425.000,00
II <u>Pelaksanaan Pekerjaan</u>						
1	Penarikan dan pemasangan kabel dari ruang trafo genset ke ruang operator, instalasi kabel	1,0	ls	ls	300.000,00	300.000,00
2	Perakitan panel alarm, setting alarm	1,0	ls	ls	1.000.000,00	1.000.000,00
					Jumlah II	1.300.000,00
Terbilang : Lima Juta Tujuh Ratus Dua Puluh Lima Ribu Rupiah					Jumlah I + II	5.725.000,00
					TOTAL	5.725.000,00
					Dibulatkan	5.725.000,00

Disahkan Oleh,

Ali Ismail Siregar
Kadiv. Perencanaan Air Minum

Diketahui Oleh,

Dedi Gusman
Kadiv. Transmisi Distribusi

Medan, Desember 2024

Dihitung oleh


Julfan Fadhi
Kabid. Operasional Pompa